

**Monroe County  
Sidewalk ADA Transition Plan  
December 2022**

Introduction

Monroe County is the maintaining agency for local (not state) roads and bridges in the unincorporated county. Roadway improvement projects are managed by Monroe County Engineering Department staff with the Director of Engineering Services having responsibility for implementing improvements.

The scope of services for county roadway and drainage improvement projects includes updating all sidewalks within project limits to current ADA standards and constructing new ADA compliant sidewalks as needed based on staff evaluation and/or public input.

Evaluation

Monroe County Engineering staff identified sidewalks for which Monroe County is responsible and performed a windshield survey to assess current conditions. Table 1 lists Monroe County sidewalks by Key. Deficiencies that were noted included lack of curb ramps or non-compliant curb ramps, lack of compliant detectable warning surface and in some cases insufficient sidewalk width.

Schedule

Sidewalks are upgraded to current ADA standards as part of overall roadway improvement projects. Sidewalks that have been identified as deficient will be upgraded to be ADA compliant in future projects.

**Table One  
Monroe County  
Sidewalk Inventory**

Key	Street Name	Start/End	One or Both Sides of road	Length	Notes	ADA Upgrade Scheduled (Est. Construction Start)
Stock Island	Cross Street	US 1 to 5th Avenue	West side only	1,230 ft	New and reconstructed sidewalk in SI I project	<b>completed 12_2018</b>
Stock Island	Balido Street	County Rd to 5th Ave.	Both sides	490 ft each side	narrow, flush with road no detectable warning surface	Under Evaluation
Stock Island	County Road	Cross St to Balido Terr.	South side only	500 ft	narrow, flush with road no detectable warning surface	Under Evaluation
Stock Island	Balido Terrace	County Rd to house #410	East side only	250 ft	discontinuous, narrow, no detectable warning surface	Under Evaluation
Stock Island	5th Avenue	Cross St	North side only	85 ft	high curb edge (>6"), upgraded ADA compliant	<b>completed 12_2018</b>
Stock Island	5th Avenue	450 ft. from E. end to Shrimp Road	south only	2,400 ft.	5 ft. wide ADA compliant sidewalk constructed in SI I project	<b>completed 12_2018</b>
Stock Island	Cross Street	5th Ave to 6th Ave	East side only	90 ft	narrow, no detectable warning on south end at 6th Ave	Under Evaluation
Stock Island	6th Avenue	Cross St to 5th St.	North side only	650 ft	not continuous, narrow, no detectable warning surface	Under Evaluation
Stock Island	5th Street	5th Ave to 6th Ave	West side only	90 ft	narrow, no detectable warning on south end at 6th Ave	Under Evaluation
Stock Island	5th Street	US 1 to 5th Avenue			new ADA compliant sidewalk constructed in SI I Project	<b>completed 12_2018</b>
Stock Island	MacDonald Avenue	US1 to Fire Station	Both sides	2000 ft each side	not continuous on north side (to be upgraded)	<b>completed 1-2020</b>
Stock Island	Maloney Avenue	MacDonald Ave to end	Both sides	4000 ft each side	to be upgraded and made ADA compliant	<b>completed 1-2020</b>
Stock Island	Shrimp Road	5th Avenue to 550 ft. south	West side only	550 ft.	constructed from 5th Ave. to Bernstein Park Parking Lot	<b>Completed 9-2018</b>
Key Haven	Allamanda Avenue	Key Haven Rd to Allamanda Terr.	Both sides	1600 ft	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Amaryllis Drive	Allamanda Ave to end	Both sides	790 ft each side	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Arbutus Drive	Allamanda Ave to end	Both sides	790 ft each side	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Azalea Drive	Allamanda Ave to end	Both sides	790 ft each side	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Aster Terrace	Allamanda Ave to end	Both sides	790 ft each side	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Allamanda Terrace	Allamanda Ave to end	Both sides	790 ft each side	sidewalk flush with road (no curb)	Under Evaluation
				1075 ft north side 700 ft south side	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Key Haven Terrace	Allamanda Ave to end	Both sides			
Key Haven	Key Haven Road	Allamanda Ave to Bougainvillea Ave	NE side only	1670 ft	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Bougainvillea Avenue	Key Haven Rd to Beachwood Dr	Both sides	850 ft each side	sidewalk flush with road (no curb); not continuous	Under Evaluation
Key Haven	Bamboo Terrace	Bougainvillea Ave to end	Both sides	200 ft each side	sidewalk flush with road (no curb)	Under Evaluation
				370 ft NE side 100 ft SW side	sidewalk flush with road (no curb); not continuous - large gaps in coverage	Under Evaluation
Key Haven	Birchwood Drive	Bougainvillea Ave to Bamboo Terr.	Both sides			
Key Haven	Bamboo Terrace	end to end	Both sides	900 ft each side	sidewalk flush with road (no curb)	Under Evaluation
				330 ft NE side 550 ft SW side	sidewalk flush with road (no curb); not continuous - large gaps in coverage	Under Evaluation
Key Haven	Beachwood Drive	Bougainvillea Ave to Bamboo Terr.	Both sides			
Key Haven	Key Haven Road	Bougainvillea Ave to Cypress Ave	Both sides	725 ft each side	sidewalk flush with road (no curb)	Under Evaluation
Key Haven	Cypress Ave, Cactus Dr, Cypress Terr, Coconut Dr, Driftwood Dr, Evergreen Dr, Floral Ave	Varies	Varies	Varies	Various sized areas of sidewalk coverage (range from 50ft to 450ft long); sidewalk flush with road (no curb)	Under Evaluation
Duck Key	Duck Key Drive	south of bridge to Simran Ln (east) & Greenbriar Rd (west)	Both	1,760 ft. east side 2,000 ft. west	Shared use path that is flush with ground needs detectable warnings	Under Evaluation
Key Largo	US 1 Bayside	Approx. MM106 to MM 100	bayside only	6 miles	Shared use path constructed in 2016 ADA compliant	Completed in 2-2016