BOARD OF COUNTY COMMISSIONERS

AGENDA ITEM SUMMARY

Meeting Date: $4-16-03$	Division: Public Works			
Bulk Item: Yes No X	Department: Engineering			
AGENDA ITEM WORDING: Approval of	f paved pathways along Pirates Road, Little Torch			
Pirates Road. The biologist said that would wetlands. A path contiguous with the road constructed on each side of Pirates Road to	biologist concerning the construction of a separated path along d not be allowed due to the impact on the mangroves and will avoid wetlands. However, the path would need to be conform with bike/pedestrian standards and motor vehicle n each side of Pirates Rd. The cost to do this is \$96,030.00.			
	N: At the last BOCC meeting, the Board directed staff to ian path along Pirates Road and incorporate it into the 7 Year			
CONTRACT/AGREEMENT CHANGES:	N/A			
STAFF RECOMMENDATION: Approva paved path on both sides contiguous with Pir into the next year's schedule.	al to widen Pirates Rd. four feet on each side to allow for a ates Rd. (similar to paved shoulders) and incorporate the work			
TOTAL COST: \$96,030.00	BUDGETED: Yes NO X Proposed for next year with Gas Tax Revenue			
Cost to County: \$96,030.00				
REVENUE PRODUCING: YES NO	O AMOUNT PER MONTH YEAR			
APPROVED BY: County Arry. Item Prepared by:	OMB/Purchasing Risk Management			
David S. Koppel, P.E., C	County Engineer			
DIVISION DIRECTOR APPROVAL:	Dent Pierce, Division Director			
DOCUMENTATION : Included X T	o Follow Not Required			
DISPOSITION:	AGENDA ITEM#			

Pirates Road, Little Torch

Paved Pathway with Median

		·		
Item Description	Qty	Totals	Unit Price	Sub Total
General Provisions		1 ea	\$12,000.00	\$12,000.00
Maintenance of Traffic		l ea	\$4,000.00	\$4,000.00
Site Work		l ea	\$15,000.00	\$15,000.00
Asphalt Quantity	6' wide for 4304'	2869 yd²	\$7.25	\$20,800.25
Limerock Base	1650 yd ³ x 6"	1650 yd3	\$10.00	\$16,500.00
Additional Limerock (Shoulder/Fill)	4304'x3'x2'	957 yd ³	\$30.00	\$28,710.00
Silt Fence	4304'	4310 ft	\$2.70	\$11,637.00
Vegetation Removal				\$5,000.00
bike diamond	23	23 ea	\$35.00	\$805.00
sign removal/relocation	6	6 ea	\$150.00	\$900.00
Engineering Fee	1	l ea	\$3,000.00	\$3,000.00

Total: \$118,352.25

Paved Pathway attached to Roadway

Description	Qty	Totals	Unit Price	Sub Total
General Provisions		1 ea	\$12,000.00	\$12,000.00
Maintenance of Traffic		1 ea	\$4,000.00	\$4,000.00
Site Work		1 ea	\$15,000.00	\$15,000.00
Limerock Base	825 yd2	825 yd ²	\$10.00	\$8,250.00
Asphalt Quantity	6' wide for 2454'	1636 yd²	\$7.25	\$11,861.00
	4' wide for 1850*	822 yd ²	\$7.25	\$5,959.50
Silt Fence	4304'	4310 ft	\$2.70	\$11,637.00
Vegetation Removal				\$5,000.00
6" White Thermo	4304 ft	4304 ft	\$0.65	\$2,797.60
bike diamond	23	23 ea	\$35.00	\$805.00
sign removal/relocation	6	6 ea	\$152.00	\$912.00
Engineering	1	1 ea	\$2,800.00	\$2,800.00
			Total:	\$81,022.10

Pirates Road, Little Torch

Paved Pathway, 4 Feet on Each Side

Item Description	Qty	Totals	Unit Price	Sub Total
General Provisions		1 ea	\$12,000.00	\$12,000.00
Maintenance of Traffic		1 ea	\$4,000.00	\$4,000.00
Site Work		1 ea	\$15,000.00	\$15,000.00
Asphalt Quantity	(4' wide for 4304') x 2	3826 yd²	\$7.25	\$27,738.50
Limerock Base	825 yd ³ x 6"	825 yd3	\$10.00	\$8,250.00
Additional Limerock (Shoulder/Fill)	160 yd ³	160 yd ³	\$30.00	\$4,800.00
Silt Fence	4304'	4310 ft	\$2.70	\$11,637.00
Vegetation Removal			\$1,000.00	\$1,000.00
6" White Thermo	8608 ft	8608 ft	\$0.65	\$5,595.20
bike diamond	46	46 ea	\$35.00	\$1,610.00
sign removal/relocation	6	6 ea	\$150.00	\$900.00
Engineering	1	1 ea	\$3,500.00	\$3,500.00
			Total:	\$96,030.70